



Whitecube Industries

Fine concrete made in Britain

PROJECT:

Multi Storey Car Park Project (DWTC)

LOCATION: Dubai international Convention and Exhibition Centre (DICEC) / Dubai World Trade Centre, Dubai, UAE

CLIENT: ECC McLaren Joint Venture

CONSULTANTS : Parsons International Ltd

MAIN CONTRACTOR: ECC McLaren Joint Venture

WHITECUBE BRIEF: Supply of UHPC Flat and curved Panels to external walls of carpark

SQM: 250sqm

MOULDS: RECKLI

MOULD PATTERN: 2/154 Venta

UHPC PANEL SUPPLY: Whitecube Holdings FZC

INSTALLATION: TSPC LLC

INSTALLATION METHOD: Chemical (MAPEI Adesilex P9) and Mechanical (Fischer Anchor and SS screw) fix

TIMESCALES: Manufacturing – 120 days, Installation – 60 days

PANEL SIZE / WEIGHT: 1240mm x 1200mm x 10-28mm profile/45kgs/sqm



The Site



RECKLI rubber mould



Pouring UHPC into mould



Panels installed, joints filled



Undercoat



Job done

WHITECUBE INDUSTRIES LIMITED
The Old Storage Building, Hendl Farm,
Groombridge, TN3 9NU
Tel: 01892 860406
info@whitecubeindustries.co.uk

www.whitecubeindustries.co.uk